

Addendum #1

RFP #CC601-25

2025 MISCELLANEOUS ASPHALT REHABILITATION

BID OPENING HAS BEEN MOVED:

1. The location of the bid opening has been moved to room 404 in the Gateway Building on the Casper College Campus. The date and the time is remaining the same.

ADDITIONS AND CHANGES TO BID DOCUMENTS:

1. Added specification section for geotextile fabric – see ADDENDUM ATTACHMENT #1 – GOTEXTILE FABRIC
2. Added specification section for grading – see ADDENDUM ATTACHMENT #2 – GRADING
3. Aggregate Base Course Specification: Clarification that road base course material may have a maximum of 30% recycled material and shall meet the following gradation:
 - a. **1-1/2 Inch:** 100.
 - b. **1 Inch:** 90 to 100.
 - c. **1/2 Inch:** 60 to 85.
 - d. **No. 4:** 40 to 65.
 - e. **No. 8:** 30 to 55.
 - f. **No. 200:** 3 to 15.
4. Aggregate base course specifications: NO onsite crushing of base shall be allowed.
5. Mill and overlay specification: Clarification that 2” overlay for area 2 shall not installed for a minimum period of 7 days after crack sealant is applied.
6. Crack seal specification: Clarification that all sealant shall be installed as “Recessed Configuration” according to Section 4.5.1-part D, Item 2

QUESTIONS AND ANSWERS FROM PRE-BID MEETING:

1. Question was raised about the weight of separation fabric required.
 - a. 8oz is required.
 - b. Spec listed above and attachment.
2. Question was raised about striping of existing curb and gutter.
 - a. No striping of existing curb and gutter will be required. Only parking lot striping.
3. Question was raised about color of concrete required for the new curb in Area 1.
 - a. Concrete shall be standard gray.

4. Project award will be based on the bid total for Areas 1, 2, 3, and 4. Contractors shall include prices for Alternates 1 and 2, but these will not factor into the award of the project. Alternates will be accepted after the project award depending on budget.
5. Use of campus restrooms and facilities will not be allowed by contractor crew members. Contractor shall provide portable restrooms.
6. Contractor awarded the project shall coordinate with Mitch Masters with Campus Facilities to determine scheduling of construction activities around summer campus camps and activities. Conflicts are not anticipated at this time with any project areas.

A handwritten signature in blue ink that reads "Shane Pulliam". The signature is written in a cursive, flowing style.

Shane Pulliam
Director of Procurement

shane.pulliam@caspercollege.edu

Ph: 307-268-2633

Fax: 307-268-2880